

Job Number		Well ID	Drilling Team/Contractor
10526-Tamworth Forest Road LFG Constr		C17	Landfill Drilling
Well Type		Responsible Person	Location
Gas		Andrew Keys	Tamworth
Well Completion Detail		Approved Drill Depth (mBGL)	Well Casing Diameter (mm)
		15	160
Length of Riser (m)		Waste Stream and Comments	
Ground/Liner Level ↓		0 - 1m Clay	
Well Seal Length (m)		1 - 5m Dry Domestic Waste	
4		5 - 10m Damp Domestic Waste	
Plain Pipe Length (m)		10 - 15m Wet Sandy Domestic Waste	
4.5		Finished hole off with Orga	
Length of Gravel Above Last Perforation (m)		Plastic Seal (Yes/No)	
.5		Yes	
Length of Gravel Below Last Perforation (m)		Length of Perforated Pipe (m)	
10.5		10.5	
End Cap			
Well Completion Summary			
Depths are Measurements of Metres Below Ground Level (mBGL) - Ground Level = 0			
Plain Pipe Start Depth (mBGL)	0	Completed Drilling Depth (mBGL)	Well Seal Type
Plain Pipe End Depth (mBGL)	4.5	15	Clay/Bentonite
Perf Pipe Start Depth (mBGL)	4.5	Completed Well Casing Depth (m)	Plastic Seal Type
Perf Pipe End Depth (mBGL)	15	15	Bag
Well Seal Start Depth (mBGL)	0	Well Casing Rating (PN)	End Cap Type
Well Seal End Depth (mBGL)	4	16	Butt-Welded
Gravel Start Depth (mBGL)	4	Location Left Clean (Yes/No)	Responsible Person Sign Off
Gravel End Depth (mBGL)	15	Yes	