

Job Number		Well ID		Drilling Team/Contractor	
10526-Tamworth Forest Road LFG Constr		C33		Landfill Drilling	
Well Type		Responsible Person		Location	
Gas		Andrew Keys		Tamworth	
Well Completion Detail		Approved Drill Depth (mBGL)		Well Casing Diameter (mm)	
		15		160	
Length of Riser (m)		2			
Ground/Liner Level ↓		0 - 3.8m Clay			
Well Seal Length (m)		3.8 - 5m Damp Domestic Waste			
4		5 - 10m Damp Domestic Waste			
Plain Pipe Length (m)		10 - 15m Wet Sandy Domestic Waste			
4.5					
Length of Gravel Above Last Perforation (m)		Plastic Seal (Yes/No)			
.5		Yes			
Length of Gravel Below Last Perforation (m)		Length of Perforated Pipe (m)			
10.5		10.5			
End Cap					
Well Completion Summary					
Depths are Measurements of Metres Below Ground Level (mBGL) - Ground Level = 0					
Plain Pipe Start Depth (mBGL)	0	Completed Drilling Depth (mBGL)	Well Seal Type		
Plain Pipe End Depth (mBGL)	4.5	15	Clay/Bentonite		
Perf Pipe Start Depth (mBGL)	4.5	Completed Well Casing Depth (m)	Plastic Seal Type		
Perf Pipe End Depth (mBGL)	15	15	Bag		
Well Seal Start Depth (mBGL)	0	Well Casing Rating (PN)	End Cap Type		
Well Seal End Depth (mBGL)	4	16	Butt-Welded		
Gravel Start Depth (mBGL)	4	Location Left Clean (Yes/No)	Responsible Person Sign Off		
Gravel End Depth (mBGL)	15	Yes	AK		