

# As Built Drilling Log



		Gas Well ID		Construction Supervisor	
		GO68		Andrew Keys	
Job Number		Responsible Person		Location	
9991		Chris Watkins / Luke Shlecta		Erskine Park Landfill	
Drill String Detail		Approved Depth Of Drilling		Well String Diameter/Rating	
		38 m		225 mm/PN	
<div> <div>Top Of Pipe Above Ground</div> <div>1.5 m</div> </div>					
		<b>Waste Stream and Comments</b>			
Ground/Liner Level		0 - 2.4m Clay Cap/Dirt			
Plain Pipe Length m		Dry Rubbish			
4.5		Industrial Waste, No Wet Matter			
Clay Plug Depth m		Some Soil Clay Matter at 5M			
3		Dry Rubbish down to 8m			
Plain Pipe		Some Moisture present Soil and Clay			
		Back into industrial waste			
Bentonite (1000 mm)		No Rotting Matter, a little dusty down to 14m			
plastic bag base		Some Damp dirt present,			
Rock 500mm above last Perforation		Back into dry Rubbish till aproxamitly 18m where rubbish went to damp and tacky but not wet and remained constant to final depth of 38meters			
Depth of Perforation m					
33.5					
0					
0					
0					
0					
0					
0					
0					
0					
0					
0					
0					
0					
0					
0					
End Cap					
Well Completion from GL Summary					
Depth of plain well string		4.5 m			
Depth of clay plug		3 m			
Depth of Bentonite plug		1 m			
Depth of Rock		34 m			
Depth of perforated well string		33.5 m			
Date Completed		Completed Drilling Depth		Completed Well String Depth	
2016-08-26		38 m		38 m	
Bentonite Plug Completed		X		Sign Off <i>A. Keys</i>	
Location Left Clean		X			