

As Built Drilling Log



			Gas Well ID	Construction Supervisor
			GO67	Andrew Keys
Job Number			Responsible Person	Location
9991			Chris Watkins/Luke Shlecta	Erskine Park Landfill
Drill String Detail			Approved Depth Of Drilling	Well String Diameter/Rating
Top Of Pipe Above Ground	1.5 m		38 m	225 mm/PN 12.5
Ground/Liner Level			Waste Stream and Comments	
Plain Pipe Length m	Clay Plug Depth m		Clay, Soil, Sand to 1.5m	
4.5	3		Rubbish with sand soil composited down to 4.4m	
			Small amounts of Dirt and Clay, then back into Dry Rubbish down to 9m where Rubbish Became Damp	
			Some Dirt and Clay Evident till approx 10m	
	Bentonite (1000 mm)	plastic bag base	Dry Dirt impregnated Rubbish down to 15m where Rubbish became damp to 16m	
		Rock 500mm above last Perforation		
Depth of Perforation m	0	Depth Of Rock m	Dirt and Clay down to 20m	
33.5	0	34	Black sand with Rubbish to 24m wheresome moisture did s	
	0		Rubbish remained damp down to 27m where it dried up	
	0		Small amounts of dirt and Clay down to 30m	
	0		Dry Rubbish with Broken bricks and Industrial waste down t	
	0			
	0			
	0			
	0			
	0			
	0			
	End Cap			
Well Completion from GL Summary				
Depth of plain well string	4.5 m			
Depth of clay plug	3 m			
Depth of Bentonite plug	1 m			
Depth of Rock	34 m			
Depth of perforated well string	33.5 m			
Date Completed	Completed Drilling Depth	Completed Well String Depth		
2016-08-27	38 m	38 m		
Bentonite Plug Completed	X	Sign Off	A Keys	
Location Left Clean	X			