

# As Built Drilling Log



		Gas Well ID		Construction Supervisor	
		G066		Andrew Keys	
Job Number		Responsible Person		Location	
9991		Chris Watkins / Luke Shlecta		Erskine Park Landfill	
Drill String Detail		Approved Depth Of Drilling		Well String Diameter/Rating	
		38 m		225 mm/PN 12.5	
<div> <div>Top Of Pipe Above Ground</div> <div>1.5 m</div> </div>		<b>Waste Stream and Comments</b> Minimal cap at this loacation Area crrently being filled and compacted Dry Rubbish Well compacted Dirt impregnated, not possible to locate anny obviouse Laye down to 10m where Clay/Dirt went for 1m Back into Dry Rubbish with dirt impregnated Rubbish Some Moisture at 15m Closely followed by Clay/Sand Dry Rubbish to 22m where we hit a steel I beam, cut through at the cost of teeth, Note this took about an hour to drill Thr Also an Hour lost to change teeth... Dry Rubbish down to 25m where we cut more steel away Dry Rubbish continued down to 30m where a layer of bricks etc was present, Followed by some loose dirt at 32m Dry Rubbish continued down to final depth of 38nm			
<div> <div>Ground/Liner Level</div> <div>4.5 m</div> </div>					
<div> <div>Plain Pipe Length m</div> <div>4.5</div> </div>		<div> <div>Clay Plug Depth m</div> <div>3</div> </div>			
<div> <div>Plain Pipe</div> </div>					
<div> <div>Bentonite (1000 mm)</div> </div>		<div> <div>plastic bag base</div> </div>			
<div> <div>Rock 500mm above last Perforation</div> </div>					
<div> <div>Depth of Perforation m</div> <div>33.5</div> </div>		<div> <div>Depth Of Rock m</div> <div>34</div> </div>			
<div> <div>0</div> <div>0</div> <div>0</div> <div>0</div> <div>0</div> <div>0</div> <div>0</div> <div>0</div> <div>0</div> <div>0</div> <div>0</div> <div>0</div> <div>0</div> <div>0</div> <div>0</div> </div>					
<div> <div>End Cap</div> </div>					
Well Completion from GL Summary					
Depth of plain well string		4.5 m			
Depth of clay plug		3 m			
Depth of Bentonite plug		1 m			
Depth of Rock		34 m			
Depth of perforated well string		33.5 m			
Date Completed		Completed Drilling Depth		Completed Well String Depth	
2016-08-27		38 m		38 m	
Bentonite Plug Completed		X		Sign Off	
Location Left Clean		X			
				AKES	