

Job Number	Date Drilled	Well ID	Drilling Team/Contractor
11751-MRL LF	2019-07-23	3B-004 / 3-489	Civil group andy
Well Type		Responsible Person	Location
Gas		Leigh Brown	Melbourne Regional Landf
Well Completion Detail		Approved Drill Depth (mBGL)	Well Casing Diameter (mm)
		10	225
Length of Riser (m)		Waste Stream and Comments	
Ground/Liner Level ↓	2	0m - 0.6m - clay cap / dirt	
Well Seal Length (m)	<p>P L A I N  P I P E</p>	Plain Pipe Length (m)	0.6m - 2.7m - dry rubbish / fabrics
			2.7m - 4.6m - dry rubbish
			4.6m - 6.8m - damp rubbish / carpet
			6.8m - 8.7m - damp rubbish / tree branches
			8.7m - 10m - damp rubbish / fabrics / plastics
Length of Gravel Above Last Perforation (m)	↓Gravel↑	Plastic Seal (Yes/No)	
1		Yes	
Length of Gravel Below Last Perforation (m)	↓Gravel↑	Length of Perforated Pipe (m)	
			End Cap
Well Completion Summary			
Depths are Measurements of Metres Below Ground Level (mBGL) - Ground Level = 0			
Plain Pipe Start Depth (mBGL)	0	Completed Drilling Depth (mBGL)	Well Seal Type
Plain Pipe End Depth (mBGL)	4	10	Clay/Bentonite
Perf Pipe Start Depth (mBGL)	4	Completed Well Casing Depth (m)	Plastic Seal Type
Perf Pipe End Depth (mBGL)	10	10	Disc
Well Seal Start Depth (mBGL)	0	Well Casing Rating (PN)	End Cap Type
Well Seal End Depth (mBGL)	3	16	Butt-Welded
Gravel Start Depth (mBGL)	3	Location Left Clean (Yes/No)	Responsible Person Sign Off
Gravel End Depth (mBGL)	10	Yes	

Photo - Take Photo of Completed Well

